

MECO Direct Cost – k\$'s

WBS Number	Description	Old Total w/Cont	Reduced W/Cont
1.4.4	MECO A-Line	\$9,459	\$7,657
1.4.4.1	Project Support and Integration	\$1,584	\$1,584
1.4.4.2	MECO Proton Beam Line	\$4,592	\$3,317
1.4.4.3	Instrumentation	\$1,037	\$898
1.4.4.4	A-Line Security Modifications	\$332	\$332
1.4.4.5	Controls	\$245	\$163
1.4.4.6	MECO Experiment	\$1,671	\$1,363

- **Equipment Removal (-\$327k):** This may impact construction schedule if \$'s for HEP removal don't come when needed.
- **Use AGS inventory for Cosmic Ray Shield heavy concrete (-\$490k):** MECO's cosmic ray veto counters may have slightly higher background rates.

- **Use existing datacon controls for power supplies (-\$374k): Reduced PS control capabilities (ramp functions?, time stamps? Etc?), decrease in PS control reliability, and small chance of need for “engineered fix” to replace obsolete electronic parts during operations.**

- **Replace PLC magnet monitor system with existing “green box” (-\$40k): Small increase in trouble shooting time when magnets fail.**
- **Use existing vacuum pumps for beamline vacuum (-\$43k): Small decrease in reliability of vacuum system.**

- **Remove BPM's (-\$138k):** Beamline vacuum must be adequate to operate EPM's. Possible reduction in beam position resolution with EPM.
- **Dave Gassner looking at more instrumentation reductions.**
- **Controls reduction due to use of datacon for PS control (-\$81k):** No impact

- **Use existing counting house (-\$312k): No impact on Physics. Reduced “quality of life” for experimenters. Small increase in maintenance costs during life of experiment.**